

SCHEDULE - A**Name of work : Providing RCC steps for wayout from Floating boat jetty at Boat House, Pykara.**

Sl. No.	Approx. Qty	Description of work	TNDSS & MORTH No.	Unit (In Figures and words)	Rate (In Figures and words)	Amount Rs.
1	340.00 M ³	Earthwork excavation for foundation in all soils and sub soils and to full depths may be directed except in rock requiring blasting inclusive of shoring shuttering, bailing out water wherever necessary and depositing the surplus earth within the compound in places shown by the departmental officers with an initial lead of 10mts and clearing and leveling the site etc complete complying with standard specification.	20A & 95	1 Cu.m (One Cubic metre only)		
2	35.00 M ³	Filling the river sand to the foundation and basement including watering and consolidating as per standard specification.	18	1 Cu.m (One Cubic metre only)		
3	35.00 M ³	Plain cement concrete 1:5:10 (one cement five sand and ten jelly)using 40mm HBS jelly of BSS gauge for foundation and flooring as per standard specifications	28	1 Cu.m (One Cubic metre only)		

Sl. No.	Approx. Qty		Description of work	TNDSS & MORTH No.	Unit (In Figures and words)	Rate (In Figures and words)	Amount Rs.
4			Reinforced cement 1:11/2:3 using 20mm HBS jelly of B.S gauge for all RCC works excluding the cost of centering the cost of centering and reinforcement as per standard specification.				
	104.00	M ³	a) Up to Basement	Special	1 Cu.m (One Cubic metre only)		
5			Supplying and erecting steel CENTERING including necessary supports for plane surfaces for Reinforced cement concrete works such as column footings, column pedestals, plinth beams, grade beam, staircase steps etc., strutting using mild steel sheets of size 90cm x 60cm and 10BG stiffened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding, laid over silver oak joists of size 10cm x 6.5cm spaced at about 75 cm centre to centre or at suitable intervals etc complete in all floors complying with standard specification.(Payment for centering shall be given after the concrete is laid)				
	455.00	M ²	a) Roof slab , Column & beam	Special	1 Sq.m (One Square meter only)		

Sl. No.	Approx. Qty	Description of work	TNDSS & MORTH No.	Unit (In Figures and words)	Rate (In Figures and words)	Amount Rs.
6	100.00	Qtl	Supplying fabricating and placing in position of MS or RTS rods for all RCC works including cost of steel binding wire and labour charges to fabrication but excluding the cost of concrete and centering as per standard specification.	Special	1 Qtl (One Quintal only)	
7	505.00	M ²	Plastering with cement mortar 1:3 (1 cement and 3 sand) 10 mm thick to the RCC exposed faces with standard specification.	Special	1 Sq.m (One Square meter only)	
8	115.00	M ²	Laying flooring tiles with new CC laminated tiles (like dora, duracrete, eurocon tiles)antiskid 20mm thick of approved quality, colour and design laid in cement mortar 1:3, 20 mm thick and pointing the joints with same colour cement mixed with pigment at the rate of 0.40kg/M ² to the full depth of tiles as per standard specification.	Special	1 Sq.m (One Square meter only)	
9	505.00	M ²	Painting two coats of newly plastered wall surface with ready mixed Exterior emulsion paint of first class quality and of approved colour over a priming coat including thorough scrapping, clean removal of dirt, and including necessary plaster of paris putty, wherever required etc., complete complying with standard specification.	Special	1 Sq.m (One Square meter only)	

Sl. No.	Approx. Qty		Description of work	TNDSS & MORTH No.	Unit (In Figures and words)	Rate (In Figures and words)	Amount Rs.
10	120.00	RM	Supplying and fixing of MS handrails of 0.90M height which is made of 2" MS pipe as main runner 2" MS pipe as vertical post at each and every three feet interval and horizontal runner using 2" MS pipe 1 rows below the main runner. The rate includes the cost of all materials, conveyance charges, buffing, welding labour charges and two coat of best approved frist quailty and colour of synthetic enamel paint over one coat of red oxide etc., complete.	Special	1 M (One Running metre only)		
Sub TOTAL							
GST 18%							
TOTAL							